

BHS Renovation Plan


Presentation to NPAs - July , 2020



BURLINGTON
SCHOOL DISTRICT

Introduction

Stages of Design

- Conceptual Design (pre-bond vote)
- Schematic Design (Completed and approved in April, 2020)
- Design Development (We are here) 
- Construction Documents (Scheduled for completion in early 2021)

Details are subject to change as we move through the design process

Schematic Design

© 2020, Black River Design, Architects. All rights reserved.



AERIAL VIEW - NO GALLERIA NO GYM




AERIAL VIEW FROM SOUTH EAST



PROPOSED ENTRY VIEWS WITH/OUT AUXILIARY GYM
06/29/20 scale: 3" = 1'-0"
BURLINGTON HIGH SCHOOL RE-ENVISIONING

BLACK RIVER DESIGN ARCHITECTS


Schematic Design




Project Highlights

- Accessibility and ADA compliance/enhancements
- Consolidation of classroom instruction, student support and departmental spaces
- Creation of maker spaces conducive for new technologies
- Addresses identified deferred maintenance
- New windows, roof and insulation to improve energy efficiency and reduce future costs
- New HVAC with AC, lighting and stormwater management
- Enhanced building safety and security
- New fire safety automatic sprinkler system installed


Schematic Design Site Plan




Schematic Design Floor Plans




BHS - LEVEL 7 / BTC - LEVEL 3




BHS - LEVEL 5




BHS - LEVEL 3 / BTC - LEVEL 1 (MAIN ENTRY LEVEL)




BHS - LEVEL 6 / BTC - LEVEL 2



BHS - LEVEL 4



BHS - LEVEL 2



BHS - LEVEL 1




PROPOSED FLOOR PLANS
02/28/20 scale: 1" = 100'-0"
BURLINGTON HIGH SCHOOL RE-ENVISIONING




BLACK RIVER DESIGN ARCHITECTS


Schematic Design Floor Plans




BHS - LEVEL 7 / BTC - LEVEL 3




BHS - LEVEL 5




BHS - LEVEL 3 / BTC - LEVEL 1 (MAIN ENTRY LEVEL)




BHS - LEVEL 6 / BTC - LEVEL 2



BHS - LEVEL 4



BHS - LEVEL 2



BHS - LEVEL 1



PROPOSED FLOOR PLANS
02/28/20 scale: 1" = 100'-0"
BURLINGTON HIGH SCHOOL RE-ENVISIONING



BLACK RIVER DESIGN ARCHITECTS

Proposed vs. Existing Square Footage

Overall Project Gross Area (approximate):

- Existing – 240,000 sf
- Proposed – 270,000 sf
 - Renovation - 192,000 sf
 - New Addition - 79,000 sf

Proposed vs. Existing Program

Number and Size of General Classrooms:

General classrooms are classrooms scheduled for “non-lab” classes including, but not limited to: Math, History, Social Studies, English, English Language, Special Ed. General classrooms sizes are sized to allow for a capacity of approximately 30 sf / student and include casework within each classroom.

- Existing – 39 (Average Size - 695 sf)
- Proposed – 42 (Average Size – 730 sf)

Proposed vs. Existing Program

Number of Small Group Classrooms:

Small Group Classrooms are classrooms sized for seminars, conferences, or small group work (not included in classroom count above).

- Existing – 0
- Proposed - 4

Proposed vs. Existing Program

Number of Conference Rooms:

Conference rooms are spaces available to faculty and staff for meetings and other working groups. These spaces are within larger support suites and include conference rooms within administration and guidance, library breakout rooms, student support group room, and professional development conference room.

- Existing: 1
- Proposed: 6

Proposed vs. Existing Program

Administration and Support Spaces:

Support spaces include: Administration and Guidance Suite, Health Services, MLL, Special Education, Para Lounge, Intensive Special Needs Suite, Student Support, Professional Development Suite, Faculty Lounge and Storage, I.T. Offices.

- Existing – 14,600 sf
- Proposed – 21,200 sf

Proposed vs. Existing Program

Extracurricular and Lab Spaces:

Extracurricular and lab spaces include: Science labs, Fine Arts, Design / Technology, Library, Athletics / PE, Music, Food Lab, District on Top, Cafeteria / Kitchen, and Theater.

- Existing: 78,000 sf
- Proposed: 90,150 sf

Proposed vs. Existing Program

BTC Spaces:

Program spaces associated with BTC.

- Existing: 35,000 sf
- Proposed: 35,900 sf

Project Scope Reductions

- **Eliminate Canopy over Bike Parking**
- **Eliminate Gym Floor Replacement**
- **Eliminate Auxiliary Gym (to be designed and bid as an alternate)**
- **Reduce F Building Renovations**
 - ★ **Maintains Full ADA Compliance Upgrades**
 - ★ **Maintains New and Remodeled Restrooms**
 - ★ **Maintains Elevator Replacement**

Schematic Design Reconciled Estimate

Construction Cost of Work

BURLINGTON HIGH SCHOOL	SD ESTIMATES			
4/10/2020	270,644 GSF	273,750 GSF	270,644 GSF	
	W-T ESTIMATE	3RD PARTY ESTIMATE	W-T RECONCILED ESTIMATE	REC.% DIFF.
COST OF CONSTRUCTION WORK				
Existing Conditions	\$ 2,164,553	\$ 1,692,370	\$ 1,798,488	
Concrete	\$ 1,527,538	\$ 1,705,658	\$ 1,687,549	
Masonry	\$ 1,693,472	\$ 1,688,963	\$ 1,743,472	
Metals	\$ 3,554,542	\$ 3,484,406	\$ 3,507,383	
Wood, Plastics, and Composites	\$ 112,470	\$ 150,456	\$ 162,470	
Thermal & Moisture Protection	\$ 5,452,994	\$ 5,341,616	\$ 5,254,630	
Openings	\$ 4,190,620	\$ 4,448,418	\$ 4,204,520	
Finishes	\$ 5,059,207	\$ 5,484,861	\$ 5,242,078	
Specialties	\$ 898,652	\$ 888,288	\$ 898,702	
Equipment	\$ 833,835	\$ 876,505	\$ 883,335	
Furnishings	\$ 1,166,628	\$ 1,393,835	\$ 1,331,952	
Special Construction	\$ -	\$ -	\$ -	
Conveying Systems	\$ 540,000	\$ 637,500	\$ 624,000	
Fire Suppression	\$ 1,078,198	\$ 1,339,724	\$ 1,078,198	
Plumbing	\$ 2,560,308	\$ 3,296,120	\$ 2,560,308	
HVAC	\$ 14,471,591	\$ 13,702,854	\$ 14,471,591	
Electrical	\$ 9,156,321	\$ 9,748,961	\$ 9,156,321	
Earthwork	\$ 1,352,339	\$ 1,746,427	\$ 1,352,339	
Exterior Improvements	\$ 1,840,661	\$ 1,771,282	\$ 2,218,344	
Site Utilities	\$ 1,615,303	\$ 1,388,391	\$ 1,554,206	
SUBTOTAL - COST OF CONSTRUCTION WORK	\$ 59,269,232	\$ 60,786,635	\$ 59,729,886	1.8%

Schematic Design Reconciled Estimate

General Conditions

BURLINGTON HIGH SCHOOL		SD ESTIMATES								
4/10/2020										
	W-T ESTIMATE		3RD PARTY ESTIMATE		W-T RECONCILED ESTIMATE		REC.% DIFF.			
GENERAL CONDITIONS (descriptions for reconciled estimate only)										
WT General Requirements	4.00%	\$	1,976,688	4.50%	\$	2,299,458	4.00%	\$	2,019,474	
Subcontractor P&P Bonds	1.10%	\$	543,589	1.50%	\$	766,486	1.10%	\$	555,355	
CM Construction Contingency	fixed	\$	200,000	5.00%	\$	2,554,954	fixed	\$	200,000	
WT General Conditions	fixed	\$	2,014,000	fixed	\$	2,014,000	fixed	\$	2,014,000	
WT P&P Bond (based on COW plus GCs plus Est. & Esc. Cont.)	0.75%	\$	406,136	1.20%	\$	613,189	0.75%	\$	429,714	
WT Fee & Liability Insurance (based on COW plus GCs plus Est. & Esc. Co	2.75%	\$	1,500,334	2.75%	\$	1,405,225	2.75%	\$	1,599,235	
Total General Conditions		\$	6,640,748		\$	9,653,311		\$	6,817,777	
SD Estimating Contingency (based on COW only)	1.25%	\$	617,715	0.00%	\$	-	1.25%	\$	631,086	
Labor & Material Escalation Contingency (based on COW only)	2.75%	\$	1,358,973	2.75%	\$	1,405,225	2.75%	\$	1,388,388	
Design Contingency (based on COW only)	0.00%	\$	-	9.00%	\$	4,598,917	5.00%	\$	2,524,342	
Owner Contingency (based on COW only)	7.64%	\$	3,773,312	0.00%	\$	-	5.00%	\$	2,524,342	
Total Contingency (not including Construction Contingency)	11.64%	\$	5,750,000	11.75%	\$	6,004,141	14.00%	\$	7,068,158	
Building Permits (based on COW only)	0.85%	\$	476,493	1.30%	\$	664,288	0.85%	\$	429,138	
TOTAL GENERAL CONDITIONS		\$	12,867,240		\$	16,321,740		\$	14,315,073	14.0%
SUBTOTAL - COST OF CONSTRUCTION		\$	62,284,440		\$	67,420,813		\$	64,801,913	4.0%

Schematic Design Reconciled Estimate

Owners Cost & Total Project Cost

BURLINGTON HIGH SCHOOL	SD ESTIMATES			
4/22/2020	270,644 GSF	273,750 GSF	270,644 GSF	
OWNER COSTS				
Consultant Fees (not including abatement consultant)	\$ 5,487,301	\$ 5,487,301	\$ 5,487,301	
Abatement Costs (including consulting fees)	\$ 1,604,700	\$ 1,604,700	\$ 1,604,700	
Zoning Permit	\$ 145,000	\$ 145,000	\$ 145,000	
Equipment	\$ 688,000	\$ 688,000	\$ 688,000	
Furniture	\$ 720,000	\$ 720,000	\$ 720,000	
Other	\$ 512,500	\$ 512,500	\$ 512,500	
TOTAL OWNER COSTS	\$ 9,157,501	\$ 9,157,501	\$ 9,157,501	0.0%
OWNER COST SAVINGS OPTIONS	PROPOSED VALUE	PROPOSED VALUE	PROPOSED VALUE	
Reduce Owner Furniture Budget	\$ (360,000)	\$ (360,000)	\$ (360,000)	
CHPS Certification	\$ (185,000)	NOT TAKEN	NOT TAKEN	
OWNER COST SAVINGS OPTIONS TOTAL	\$ (545,000)	\$ (360,000)	\$ (360,000)	0.0%
TOTAL OWNER COSTS (AFTER COST SAVINGS)	\$ 8,612,501	\$ 8,797,501	\$ 8,797,501	0.0%
TOTAL PROJECT COST	\$ 70,896,941	\$ 76,218,314	\$ 73,599,414	3.6%

Project Cost Estimate & Budget

\$70,000,000 Bond Amount

\$3,600,000 Additional Approved Funding

\$73,600,000 Available Funds

\$73,599,414 Schematic Design Estimate

Cultivating caring, creative, and
courageous people. Join the journey!



BLACK RIVER DESIGN ARCHITECTS

