BHS Renovation Plan


April 27, 2020



Schematic Design



Schematic Design




Project Highlights

- Accessibility and ADA compliance/enhancements
- Consolidation of classroom instruction, student support and departmental spaces
- Creation of maker spaces conducive for new technologies
- Addresses identified deferred maintenance
- New windows, roof and insulation to improve energy efficiency and reduce future costs
- New HVAC with AC, lighting and stormwater management
- Enhanced building safety and security
- New fire safety automatic sprinkler system installed

Schematic Design Site Plan



Schematic Design Floor Plans



Proposed vs. Existing Square Footage

Overall Project Gross Area (approximate):

- Existing 240,000 sf
- Proposed 270,000 sf
 - Renovation 192,000 sf
 - O New Addition 79,000 sf

Number and Size of General Classrooms:

General classrooms are classrooms scheduled for "non-lab" classes including, but not limited to: Math, History, Social Studies, English, English Language, Special Ed. General classrooms sizes are sized to allow for a capacity of approximately 30 sf / student and include casework within each classroom.

- Existing 39 (Average Size 695 sf)
- Proposed 42 (Average Size 730 sf)

Number of Small Group Classrooms:

Small Group Classrooms are classrooms sized for seminars, conferences, or small group work (not included in classroom count above).

- Existing 0
- Proposed 4

Number of Conference Rooms:

Conference rooms are spaces available to faculty and staff for meetings and other working groups. These spaces are within larger support suites and include conference rooms within administration and guidance, library breakout rooms, student support group room, and professional development conference room.

- Existing: 1
- Proposed: 6

Administration and Support Spaces:

Support spaces include: Administration and Guidance Suite, Health Services, MLL, Special Education, Para Lounge, Intensive Special Needs Suite, Student Support, Professional Development Suite, Faculty Lounge and Storage, I.T. Offices.

- Existing 14,600 sf
- Proposed 21,200 sf

Extracurricular and Lab Spaces:

Extracurricular and lab spaces include: Science labs, Fine Arts, Design / Technology, Library, Athletics / PE, Music, Food Lab, District on Top, Cafeteria / Kitchen, and Theater.

• Existing: 78,000 sf

Proposed: 90,150 sf

BTC Spaces:

Program spaces associated with BTC.

• Existing: 35,000 sf

• Proposed: 35,900 sf

Project Scope Reductions

- Eliminate Canopy over Bike Parking
- Eliminate Gym Floor Replacement
- Eliminate Auxiliary Gym
- Reduce F Building Renovations
 - **★** Maintains Full ADA Compliance Upgrades
 - **★** Maintains New and Remodeled Restrooms
 - **★** Maintains Elevator Replacement

Schematic Design Reconciled Estimate Construction Cost of Work

BURLINGTON HIGH SCHOOL	SD ESTIMATES						
4/10/2020	270,644 GSF		273,750 GSF		270,644 GSF		
							REC.% DIFF.
COST OF CONSTRUCTION WORK							
Existing Conditions	\$	2,164,553	\$	1,692,370	\$	1,798,488	
Concrete	\$	1,527,538	\$	1,705,658	\$	1,687,549	
Masonry	\$	1,693,472	\$	1,688,963	\$	1,743,472	
Metals	\$	3,554,542	\$	3,484,406	\$	3,507,383	
Wood, Plastics, and Composites	\$	112,470	\$	150,456	\$	162,470	
Thermal & Moisture Protection	\$	5,452,994	\$	5,341,616	\$	5,254,630	
Openings	\$	4,190,620	\$	4,448,418	\$	4,204,520	
Finishes	\$	5,059,207	\$	5,484,861	\$	5,242,078	
Specialties	\$	898,652	\$	888,288	\$	898,702	
Equipment	\$	833,835	\$	876,505	\$	883,335	
Furnishings	\$	1,166,628	\$	1,393,835	\$	1,331,952	
Special Construction	\$	-	\$	-	\$	*	
Conveying Systems	\$	540,000	\$	637,500	\$	624,000	
Fire Suppression	\$	1,078,198	\$	1,339,724	\$	1,078,198	
Plumbing	\$	2,560,308	\$	3,296,120	\$	2,560,308	
HVAC	\$	14,471,591	\$	13,702,854	\$	14,471,591	
Electrical	\$	9,156,321	\$	9,748,961	\$	9,156,321	
Earthwork	\$	1,352,339	\$	1,746,427	\$	1,352,339	
Exterior Improvements	\$	1,840,661	\$	1,771,282	\$	2,218,344	
Site Utilities	\$	1,615,303	\$	1,388,391	\$	1,554,206	
SUBTOTAL - COST OF CONSTRUCTION WORK	\$	59,269,232	\$	60,786,635	\$	59,729,886	1.8%

Schematic Design Estimate Scope Reductions & Savings

BURL	INGTON HIGH SCHOOL	SD ESTIMATES						
	4/10/2020							
		W-T ESTIMATE		3RD PARTY ESTIMATE		W-T RECONCILED ESTIMATE		REC.% DIFF.
CC	OST SAVINGS OPTIONS	PROPOSED VALUE		PROPOSED VALUE		PROPOSED VALUE		
CHPS Certification		//	ICLUDED IN OWNER	IN	INCLUDED IN OWNER		INCLUDED IN OWNER	
Canopy at Bike Parking		\$	(136,175)	\$ (136,500)		\$	(136,175)	
Student Parking Lot Scop	e	\$	(400,000)	\$	(422,417)	\$	(380,360)	
Existing Gym Floor Replac	cement	\$	(175,526)	\$	(175,526)	\$	(175,526)	
Existing Bleacher Replace	ment	\$	(269,000)	\$	(296,000)	00) \$ (269,000		
Reduce Owner Furniture	Budget	INCLUDED IN OWNER INCLUDED IN OWNER		INCLUDED IN OWNER				
	CMU to GWB at corridors/classrooms		NOT TAKEN	NOT TAKEN		NOT TAKEN		
Reduce Interior Finishes	Quartz Tile to VCT Flooring Throughout	\$	(266,200)	NOT TAKEN		NOT TAKEN		
	Reduce Carpet scope	\$	(93,400)		NOT TAKEN		NOT TAKEN	
Galleria / Enlarge B-D Cor	nnector	\$	(1,131,627)	\$	(1,077,297)	\$	(915,103)	
Reduce F Building Renova	ations	\$	(5,404,135)	\$	(5,711,928)	\$	(5,403,313)	
Alternate HVAC System w	vithout Air Conditioning		NOT TAKEN	TAKEN NOT TAKEN		NOT TAKEN		
Auxilliary Gym		\$	(1,975,969)	\$	(1,867,894)	\$	(1,963,569)	
	TOTAL COST SAVINGS OPTIONS	\$	(9,852,032)	\$	(9,687,562)	\$	(9,243,046)	4.8%
SUBTOTAL - COST OF CO	ONSTRUCTION WORK (AFTER COST SAVINGS)	\$	49,417,200	\$ 51,099,073 \$ 50,486		50,486,840	1.2%	

Schematic Design Reconciled Estimate General Conditions

BURLINGTON HIGH SCHOOL 4/10/2020	SD ESTIMATES								
	W-T ESTIMATE		TIMATE	3RD PARTY ESTIMATE		W-T RECONCILED ESTIMATE		REC.% DIFF.	
GENERAL CONDITIONS (descriptions for reconciled estimate only)									
WT General Requirements	4.00%	\$	1,976,688	4.50%	\$	2,299,458	4.00%	\$ 2,019,474	l i
Subcontractor P&P Bonds	1.10%	\$	543,589	1.50%	\$	766,486	1.10%	\$ 555,355	5
CM Construction Contingency	fixed	\$	200,000	5.00%	\$	2,554,954	fixed	\$ 200,000)
WT General Conditions	fixed	\$	2,014,000	fixed	\$	2,014,000	fixed	\$ 2,014,000)
WT P&P Bond (based on COW plus GCs plus Est. & Esc. Cont.)	0.75%	\$	406,136	1.20%	\$	613,189	0.75%	\$ 429,714	1
WT Fee & Liability Insurance (based on COW plus GCs plus Est. & Esc. Co	2.75%	\$	1,500,334	2.75%	\$	1,405,225	2.75%	\$ 1,599,235	5
Total General Conditions		\$	6,640,748		\$	9,653,311		\$ 6,817,777	,
SD Estimating Contingency (based on COW only)	1.25%	\$	617,715	0.00%	\$	*	1.25%	\$ 631,086	;
Labor & Material Escalation Contingency (based on COW only)	2.75%	\$	1,358,973	2.75%	\$	1,405,225	2.75%	\$ 1,388,388	3
Design Contingency (based on COW only)	0.00%	\$		9.00%	\$	4,598,917	5.00%	\$ 2,524,342	2
Owner Contingency (based on COW only)	7.64%	\$	3,773,312	0.00%	\$		5.00%	\$ 2,524,342	
Total Contingency (not including Construction Contingency)	11.64%	\$	5,750,000	11.75%	\$	6,004,141	14.00%	\$ 7,068,158	3
Building Permits (based on COW only)	0.85%	\$	476,493	1.30%	\$	664,288	0.85%	\$ 429,138	3
TOTAL GENERAL CONDITIONS		\$	12,867,240		\$	16,321,740		\$ 14,315,073	14.0%
SUBTOTAL - COST OF CONSTRUCTION		\$	62,284,440		\$	67,420,813		\$ 64,801,913	4.0%

Schematic Design Reconciled Estimate Owners Cost & Total Project Cost

BURLINGTON HIGH SCHOOL	SD ESTIMATES						
4/22/2020	270,644 GSF	Į.	273,750 GSF		270,644 GSF		
OWNER COSTS							
Consultant Fees (not including abatement consultant)	\$	5,487,301	\$	5,487,301	\$	5,487,301	Œ.
Abatement Costs (including consulting fees)	\$	1,604,700	\$	1,604,700	\$	1,604,700	
Zoning Permit	\$	145,000	\$	145,000	\$	145,000	
Equipment	\$	688,000	\$	688,000	\$	688,000	
Furniture	\$	720,000	\$	720,000	\$	720,000	
Other	\$	512,500	\$	512,500	\$	512,500	
TOTAL OWNER COSTS	\$	9,157,501	\$	9,157,501	\$	9,157,501	0.0%
OWNER COST SAVINGS OPTIONS	PROPOSED VALUE		PROPOSED VALUE		PROPOSED VALUE		
Reduce Owner Furniture Budget	\$	(360,000)	\$	(360,000)	\$	(360,000)	
CHPS Certification	\$	(185,000)		NOT TAKEN		NOT TAKEN	
OWNER COST SAVINGS OPTIONS TOTAL	\$	(545,000)	\$	(360,000)	\$	(360,000)	0.0%
TOTAL OWNER COSTS (AFTER COST SAVINGS)	\$	8,612,501	\$	8,797,501	\$	8,797,501	0.0%
TOTAL PROJECT COST	\$	70,896,941	\$	76,218,314	\$	73,599,414	3.6%

Additional Revenue Approved by BSD Board

*Board Memo

Apply remaining funds from the Taft School lease	\$1,100,000
Use Capital Plan proceeds already earmarked for BHS	\$500,000
Apply existing one-time funding to cover owner costs	\$2,000,000
TOTAL ADDITIONAL PROJECT FUNDS	\$3,600,000

Project Cost Estimate & Budget

\$70,000,000 Bond Amount

\$3,600,000 Additional Approved Funding

\$73,600,000 Available Funds

\$73,599,414 SD Estimate

Additional Possible Cost Savings

- Permit Fees Status
 - Originally estimated at \$819k (combined zoning & building)
 - Current fee estimate \$574k (based on conversation with zoning staff)
- Requested of City Council
 - Waive a significant portion of the permit fees (zoning and/or building)
 - Precedent in City Place fee reduction

Next Steps & Timeline

Revised Timeline - Draft

• May 1, 2020: Begin Design Development Phase

• June 2020: Resume permit inquiry and acquisition

October 2020: Begin Construction Document Phase

• May 2021: Begin bidding phase

• July 2021: Begin Construction (36 - 42 months duration)

• September 2024: Project complete

Possible Summer 2020 Project Scope

- Stand-alone electrical room
- Replace existing bleachers
- Student parking lots
- F-Building ADA upgrades
- Asbestos abatement
- Utility locating services

Cultivating caring, creative, and courageous people. Join the journey!



BLACK RIVER DESIGN ARCHITECTS



